BRUHAT BANGALORE MAHANAGARA PALIKE, BYATARAYAPURA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92
BBMP/2014-15/OW/WORK_INDENT16489

DRAFT TENDER SCHEDULE

Original / Duplicate

Issued to :

Name of Work:Providing and Fixing New Street Signage Boards in Ward No. 08, Kodigehalli Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	72.57	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	cum	75.6	
2	72.57	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	cum	73.57	
3	18.14	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregares @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5064.12	
4	54.43	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5852.52	
5	252	Supplying of MS steel name boards as per approved design and specification complete with all leads and lifts as per the direction of the Engineer-in-charge of the work (Data rate approved)	No.	5203	
6	263.61	KSRB- 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	sqm	82.08	

ಕಾರ್ಯ ಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ ಬೆಂಗಳೂರು-560092.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	263.61	KSRB- 15-18.1 : Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after thoroughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, laour complete as per specifications	sqm	28.08	
8	189000	KSRRBM800-9: Painting new letter and figures of any sshade with synthetic enamel paint black or nay other approved colour to give an even shade complete as per specifications ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half)	cm	0.7	
9	10	Providing and fixing of Ornamental name boards (providing and fixing of ornamental name boards of size 2.10x0.50m) and 2 column of size 0.15x0.15m of height 1.23m o feach boards of CC 1:1.5:3 with necessary centering and form work, smooth finishing with reinforcement etc., including fabrication charges, painting letters (Bangalore Mahanagara Palike, ward No. and BBMP Emblem) earthwork excavation, concreting and transportation charges from manufacturing yard to the wrok site etc, complete with all leads and lifts loading and unloading and any incidental charges and as per the drawing and specification and direction of the Engineer-in-charge of the work	No.	8100	

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

'DTS' ಅವರಿಂದ

Superintending Engineer
Yelahanka Zone
BBMP Bangalore-92